



MINUTES
City Council Work Session Meeting
Tuesday, December 11, 2018 City Hall- Council Chambers, 39250
Pioneer Blvd., Sandy, Oregon 97055 6:30 PM

COUNCIL PRESENT: Jeremy Pietzold, Council President, John Hamblin, Councilor, Jan Lee, Councilor, and Carl Exner, Councilor

COUNCIL ABSENT:

STAFF PRESENT:

MEDIA PRESENT:

	Page
1. Roll Call	
2. Presentation	
2.1. Informational Meeting - Waste Water Treatment Plant Design Update	3 - 54
Staff Report - 0087	
Murraysmith a Portland firm that specializes in engineering design of transportation, water, wastewater and stormwater systems presented information to council on our current wastewater treatment plant and showed what can be done to improve and expand. See attached PDF presentation.	
Please note, the video only has audio as we had a power outage and we were unable to recover video.	
Sandy WSFP CityCouncil 2018.12.10	
3. Adjourn	

Mayor, William King

City Recorder, Karey Milne

City of Sandy Wastewater System Facilities Plan Workshop

murraysmith




December 11, 2018

Meeting Purpose

- Update City Council on the status of the plan
- Provide overview of the draft plan and recommendations
- Provide a schedule for finalizing the plan including public comment and plan adoption
- Provide a schedule for implementation of recommendations

Agenda



Sandy Wastewater System Background

- WWTP History
 - **1965** – WWTP original construction
 - **1993** – Last Wastewater System Facilities Plan (WSFP)
 - **1998** – Last WWTP Upgrades completed
- Sandy is one of the fastest growing communities in Clackamas County
- Need to update and implement WSFP to address deficiencies and provide for community growth


Overview of Wastewater System



Key Issues


- High Inflow and Infiltration in the City's sanitary sewer collection system
- Existing Wastewater Treatment Plant (WWTP) has limited capacity and is located on a constrained site
- Limited discharge capacity in Tickle Creek
- City now under Mutual Agreement and Order (MAO)

Balancing Collection System and Treatment Plant Investments




2. Collection System






Flow Monitoring and Modeling




Sandy Wet-Weather Response – Basin 8


Conduit SSML0267



- 15:1 peaking factor
- Flows remain elevated

Conduit SSML0267






Cost-effectiveness of Rehabilitation Strategies

Method	% Peak I/I Removal
Mains and Laterals	65 to 88%
Mains and ROW Laterals Only	40%
Mainlines Only	12 to 16%


Method	\$/gallons removed
Mains and Laterals	0.41
Laterals Only	26.40
Mainlines Only	27.79

Long-Term Commitment to Program (example: Sweet Home, Oregon)



Initial Phases Generally Most Effective (example: Sweet Home, Oregon)

Phase	Cost	I/I reduction	\$/gallons removed
1 and 2	\$3.0M	6.4 mgd	0.47
3	\$3.1M	2.2 mgd	1.41
4	\$6.0M	2.1 mgd	2.86



Next Steps


- Smoke Testing (City-wide)
- Remove Inflow Sources
- CCTV (Basins 2 and 8)
- Develop Private I/I Policy
- Flow Monitoring




3. Regulatory Background



Winter



Summer



Permitted Discharge Concentration and Mass Load Limits

Parameter	Average Effluent Concentrations		Monthly*	Weekly*	Daily*
	Monthly	Weekly	Average lb/day	Average lb/day	Maximum lbs
BOD ₅	10 mg/L	15 mg/L	125	187	250
TSS	10 mg/L	15 mg/L	125	187	250


- Tickle Creek discharge Nov-April Only
- Three Basin Rule (OAR 340-041-0350) does not allow mass load limits increase in the Clackamas River Sub-basin.
- Based on current mass loads, 2040 design effluent BOD and TSS concentrations ~ 3.5 mg/L (much less than permitted average effluent concentrations)

Dilution Criteria Evaluation

Currently, exceeding Tickle Creek discharge limits based on NPDES dilution criteria

Need more river flow!

Deep Creek Confluence Flow is estimated to be 2.3X Tickle Creek flow at current outfall.



Dilution = $(Q_s + Q_e)/Q_e \geq 10$, where

Q_s = Tickle Creek flow measured at gauge, per Schedule B, 1.e (Note7).

Q_e = Effluent flow measured, per Schedule B, 1.b.

Summer Storage Requirements


- For the potted plants, Iseli irrigates when dry soils are observed.
- Limited irrigated in shoulder months (May & Oct).
- Issues of having available storage capacity during wet months.
- Need more pond volume to continue current summer season irrigation.



4. Alternatives



Collection System




Summary of Costs for Collection System for Peak Flow Scenarios

Item	9.0 MGD	10.5 MGD	14.0 MGD	17.5 MGD
Collection System Rehabilitation	\$31.7 M	\$17.9 M	\$6.2 M	\$0 M
Conveyance and Pump Station Upgrades	\$3.8 M	\$5.4 M	\$10 M	\$11.9 M
Total	\$35.5 M	\$23.4 M	\$16.2 M	\$11.9 M

Wastewater Treatment Plant

LEGEND


	SCENARIO 1: 9.0 MGD
	SCENARIO 2: 10.5 MGD
	SCENARIO 3: 14.0 MGD
	SCENARIO 4: 17.5 MGD
	SOLIDS UPGRADES




Summary of Costs for WWTP Upgrades for Peak Flow Scenarios

Item	9.0 MGD	10.5 MGD	14.0 MGD	17.5 MGD
Liquid Stream Upgrades	\$ 9.24 M	\$ 12.38 M	\$ 17.45 M	\$ 24.11 M
Solids Stream Upgrades	\$ 6.93 M	\$ 6.93 M	\$ 7.62 M	\$ 7.62 M
Total	\$ 16.17 M	\$ 19.31 M	\$ 25.07 M	\$ 31.73 M

Proposed Storage Ponds Location



Proposed Outfall Location



**City of Sandy, Oregon
Wastewater System Facility Plan**

Legend

- Proposed Outfall Conveyance
- Existing FM and Outfall
- Pump Station
- WWTP

Storage and Outfall Plan


September 2018 17-2137



Combined Summary of Costs

Item	9.0 MGD	10.5 MGD	14.0 MGD	17.5 MGD
Collection System Upgrades	\$35.5M	\$23.3M	\$16.2M	\$11.9M
WWTP Upgrades	\$16.2M	\$19.3M	\$25.1M	\$31.7M
Storage/Discharge Upgrades	\$19.7M	\$20M	\$20.7M	\$21.5M
Total	\$71.4M	\$62.6M	\$62.0M	\$65.1M

Combined Treatment and RDII upgrades Costs



5. Recommended Plan and Phasing

- Treatment system
- Collection system
- Discharge scenarios

So... Looking to the Sandy River

- 1993 WSFP evaluated four discharge alternatives
 1. Tickle Creek/Iseli Nursery
 2. Sandy River
 3. Clackamas River
 4. Export to Gresham
- Sandy River discharge was a close second in their evaluation




Image Source: Google Earth Pro

Considered Four Sandy River Discharge Alternatives

- **Alternative A** – Existing WWTP site with existing process approach and effluent pump station to the Sandy River
- **Alternative B** – Existing WWTP site with partial MBR conversion and effluent pump station to the Sandy River
- **Alternative C** – Existing WWTP site with primary clarifiers, anaerobic digestion, and effluent pump station to the Sandy River
- **Alternative D** – Existing WWTP site with primary clarifiers and anaerobic digestion. Satellite MBR WW Facility

Considered Four Sandy River Discharge Alternatives


- **Alternative A** – Existing WWTP site with existing process approach and effluent pump station to the Sandy River


- **Alternative B** – Existing WWTP site with partial MBR conversion and effluent pump station to the Sandy River
- ALL INVOLVE PUMPING TO SANDY RIVER
FROM EXISTING WWTP***

- **Alternative C** – Existing WWTP site with primary clarifiers, anaerobic digestion, and effluent pump station to the Sandy River

- **Alternative D** – Existing WWTP site with primary clarifiers and anaerobic digestion. Satellite MBR WW Facility

Summary of Sandy River Discharge Alternative Costs









\murray-smith.com\external\pdx_projects\17-2137 - Sandy Facility Plan\GIS\WWD\Comms\kings_CadE - Replan_Treatment.mxd [2/11/2018 9:10:28 AM] - Murray Smith





City of Sandy, Oregon
Wastewater System Facility Plan

 UGB

Effluent Improvements
 New Force Main
 New Gravity
 New HDD Siphon
 Satellite MBR
 Pump Station


 Diversion


Figure
Collection System
Improvements
Alternative D

October 2018

17-2137



Alternative D – Satellite Facility



Phased Implementation Plan

Phase 3 Wastewater CIP	Phase 1 (2018-2025)	Phase 2 (2025-2032)	Phase 3 (2032-2040)	Beyond 2040
Collection System Capacity Upgrades	\$ 4.30 M	\$ 0.90 M	\$ 0.9 M	-
Collection System RDII Reduction Program	\$ 8.34 M	\$ 1.60 M	\$ 1.80 M	\$ 12.00 M
Existing WWTP Improvements	\$ 2.50 M	\$ 19.80 M	\$ 1.40 M	-
Eastside Satellite Treatment Facility	\$ 19.20 M		\$ 3.50 M	-
Diversion Pump Station	\$ 7.20 M			
Force main to Sandy Outfall	\$ 1.00 M			
Sandy River Outfall	\$ 12.80 M			
Iseli Pump Station Upgrades/ Effluent Pump Station & Force Main to Sandy River	\$ 1.40 M			\$ 25.30 M
Total	\$ 56.74 M	\$ 22.30 M	\$ 7.60 M	\$ 37.30 M

6. Next Steps and Questions

WSFP Implementation Schedule

- January 16, 2019 – Incorporate DEQ comments into Draft Facilities Plan and re-submit
- January 18, 2019 – make Draft available to the public and solicit comments
- February 1, 2019 – DEQ submits comments on updated Draft Facilities Plan
- February 4, 2019 or February 19, 2019 – potential dates for public hearing
- Date for close of comment period (TBD)
- March 3, 2019 – Incorporate public comments and resubmit to DEQ
- March 18, 2019 – DEQ must provide provisional approval or approval of Facilities Plan
- Beyond March 2019 – Implement Recommended Plan adopted by City Council

Questions

A. – Existing WWTP site with existing process approach and effluent pump station to the Sandy River

- Upgrade existing treatment plant with existing processes
- Rehab 2 basins
- New effluent pump station to Sandy River Outfall

Item	Cost
WWTP Upgrades	\$30.5M
Collection System Upgrades	\$13.4M
Effluent Infrastructure	\$38.1M
Total	\$82.0M

B. – Existing WWTP site with partial MBR conversion and effluent pump station to the Sandy River

- Upgrade existing treatment plant with advanced treatment technology
- Rehab 2 basins
- New effluent pump station to Sandy River Outfall

Item	Cost
WWTP Upgrades	\$39.0M
Collection System Upgrades	\$13.4M
Effluent Infrastructure	\$38.1M
Total	\$90.5M

C. – Existing WWTP site with primary clarifiers, anaerobic digestion, and effluent pump station to the Sandy River

- Upgrade existing treatment plant and improve solids handling
- Rehab 2 basins
- New effluent pump station to Sandy River Outfall


Item	Cost
WWTP Upgrades	\$34.3M
Collection System Upgrades	\$13.4M
Effluent Infrastructure	\$38.1M
Total	\$85.8M

D. – Existing WWTP site with primary clarifiers and anaerobic digestion. Satellite MBR WWR

- Split treatment with Existing WWTP and New Eastside satellite treatment facility construction
- Rehab 2 basin
- Satellite treatment facility effluent pump station and New Sandy River Outfall

Item	Cost
WWTP Upgrades	\$47.3M
Collection System Upgrades	\$12.3M
Effluent Infrastructure	\$21.0M
Total	\$80.6M


Overview of Recommended Improvements




THE PLAN PROVIDES FOR:


- Avoids new trunkline to existing WWTP
- Delays major upgrades at existing WWTP and new effluent pump station and force main
- Greatest ability to phase improvements
- Long-term river discharge to support community growth

Alternative D – Process Schematic/Phasing






Existing WWTP



System Wet-Weather Response

Conduit SSML0267



- Basin 8
 - 15:1 peaking factor
 - Flows remain elevated

Conduit SSML0267

