

NOTES:

1. RESIDENTIAL DRIVEWAYS AND SIDEWALK SECTIONS THROUGH DRIVEWAYS SHALL HAVE A MINIMUM NOMINAL THICKNESS OF 6". CONCRETE STRENGTH SHALL BE 4000 PSI.
2. CONCRETE FOR COMMERCIAL USE AND ALLEY APPROACHES SHALL HAVE A MINIMUM NOMINAL THICKNESS OF 8". CONCRETE STRENGTH SHALL BE 4000 PSI.
3. CURB TRANSITIONS FOR COMMERCIAL USE AND ALLEY APPROACHES SHALL BE 5 FEET.
4. NO LIP AT GUTTER IF USED AS SIDEWALK ACCESS RAMP.
5. SEE SIDEWALK DETAILS FOR RESTRICTIONS AND SPECIFICATIONS NOT SHOWN.
6. THE 50:1 CROSS-SLOPE OF SIDEWALK IS MEASURED FROM HORIZONTAL. THE 12:1 SLOPE OF SIDEWALK TRANSITION TO DRIVEWAY/ALLEY IS RELATIVE TO THE RUNNING SLOPE OF THE SIDEWALK. THE SLOPE OF THE APRON IS MEASURED RELATIVE TO HORIZONTAL.

CITY OF SANDY

DRIVEWAY APPROACH FOR SIDEWALK WITH PLANTER STRIP

DATE: DECEMBER 2025 | DRAWING NO. 208A

FILENAME: SAN1857.DGN

LOT = 7,500 SQ. FT
BUILDING FOOTPRINT = 1,970 SQ. FT.

LOT COVERAGE:

BUILDING FOOTPRINT = 1,970 SQ. FT. /
LOT = 7,500 SQ. FT = 26.3%

IMPERVIOUS AREA:

DRIVEWAY = 405 SQ. FT.
FRONT PATH = 50 SQ. FT.
ROOF AREA = 2,156 SQ. FT.
TOTAL = 2,611 SQ. FT.

NOTES:
SUBCONTRACTOR TO SPECIFY EXACT LOCATIONS OF UTILITY STUBS



LOT #41

SITE PLAN

SCALE: 1/8"=1'-0"

MARK STEWART
HOME DESIGN

22582 SW MAIN ST.
DESIGN SUITE 309
SHERWOOD, OR 97140

(503) 701.4888 P

www.markstewart.com

Authentic Mark Stewart Original Design
Accept no substitutes

Stock Home Plans
Custom Design
Builder Marketing
Interior Design

Since 1982

These plans and the designs herein are copyrighted under Federal Law by Mark G. Stewart and Mark Stewart + Associates Inc. 2006

Important Disclosure Please Read:

The plans you have purchased are for the construction of ONE home only. Under NO circumstances is it legal to build from these plans more than once without the written consent from the designer Mark Stewart. These plans are copyrighted and it is a violation of federal copyright law to reproduce them. Mark Stewart + Associates will fully prosecute ANY violation of its copyrighted designs and plans. Furthermore it is understood that it is COMPLETELY the responsibility of the contractor to construct the home described herein, on any particular site and within the confines of the governing jurisdiction. Mark Stewart Home Design LLC takes NO responsibility for the conformance of this plan to any zoning code or any lot. These plans are prepared in accord with the most current version of the IRC.

CLIENT: GAYUDCHIK
PHASE 2
HOOD VIEW HEIGHTS

PLAN # MA-1455-1455
LOT #41

REVISIONS: MARCH 2026

PAGE SITE